


CIVILMART



M-Lock® Bridge System
**COMPLETE, COST-EFFECTIVE
BRIDGE SYSTEM**



CIVILMART



M-LOCK® Bridge System

Complete Bridge System

Cost Effective Bridge Solution

The Civilmart M-Lock® Bridge System provides a fast, simple means of bridging small to medium spans using precast, reinforced concrete components.

The system is designed for single or multispan bridges with span lengths between 7 and 15 metres. Ideal applications include rural road bridges, sub-division bridges, pedestrian bridges and utility bridges.

The M-Lock® Bridge System provides an economical and effective replacement for ageing timber bridges and combines benefits of durability and versatility with short construction times.

Cost Effective Bridge Solution

- Rural road bridges
- Sub-division bridges
- Pedestrian bridges
- Utility bridges

Modular Components

DECK

Deck planks are 1200mm wide inverted Usections with transverse end diaphragms.

They are available in the following lengths: 7m; 8m; 9m; 10m; 11m; 12m; 15m

Planks for skewed bridges (15° and 30°) are also available.

Headstocks

Precast headstocks complete with cross-fall are manufactured in multiples of 1200mm to suit standard lane widths. The headstock design accommodates either driven or rocksocketed piles.

Piles

The system is designed to incorporate a number of different piling products, principally Civilmart Duraspun® Hollow Precast Piles, square RC piles or steel UC and tubular piles.

High Quality Precast Concrete

All components are manufactured under factory controlled conditions in purpose-made moulds. This reduces the risk involved in transporting premixed concrete over long distances. Virtually no on-site wet mix is required apart from a minimal amount of grout.

Durable Structure

More durable than composite bridge systems such as timber/concrete. Precast concrete also increases durability because of the strength of the highly compacted concrete used.

Purpose Designed Product

All precast components have been designed for SM1600 live loading in accordance with the relevant structural requirements of Australian Standard Codes and accepted engineering standards and principles.

Simple Construction

After the piles are installed, the precast concrete headstock beams and planks are bolted into place. For high traffic volume bridges, transverse post-tensioning can be used in place of plank bolts. Accessories include steel guardrail or precast barriers, precast end protection beams or approach slabs and wing walls.

No Additional Surfacing Required

The system is designed to eliminate the need for in-situ toppings or wear surfaces. This speeds construction and reduces long-term maintenance costs.

Minimal Impact On Waterways

For environmentally sensitive areas, construction can proceed by reaching out from waterway banks or off a previously constructed span. No need to build coffer dams or interfere with the waterway.

Reduced Construction Time

Using a Civilmart M-Lock® Bridge results in a much reduced construction period compared to conventional bridges and other bridging systems. A crew of two or three can construct a bridge at the rate of one span per week. Disruption to the community and road users is minimised.





CIVILMART

civilmart.com.au



QLD

Civilmart Sunshine Coast	07 5493 3044
Civilmart Brisbane	07 3800 7855
Civilmart Gold Coast	07 5597 6966
Civilmart Toowoomba Tanks	07 4634 3860
Civilmart Stapylton	07 3807 4511
Civilmart CM Stapylton	07 3804 6622
Civilmart Rocla Rockhampton	07 4923 1500
Civilmart Rocla Cairns	07 4042 3400

NSW

Civilmart Sydney	02 9612 5800
Civilmart Central Coast	02 4355 6300
Civilmart Rocla Mittagong	02 4889 6000
Civilmart Rocla Grafton	02 6640 1800

VIC

Civilmart Melbourne	03 5491 8324
Civilmart Shepparton	03 5821 2810
Civilmart Shepparton Pipe	03 5821 3099
Civilmart Geelong	03 5274 1126
Civilmart Rocla Clayton	03 9549 4500
Civilmart Rocla Campbellfield	03 9292 0300
Civilmart Rocla Wodonga Poles	02 6055 7350
Civilmart Rocla Wodonga Pipe	02 6055 7300

SA

Civilmart Adelaide	08 8209 3093
Civilmart Rocla Adelaide	08 7285 1900